

B0ApF Status

Ramesh Gupta
December 10, 2025





@BrookhavenLab

Overview

- **Full length R&D magnet was built under a PBL/BNL STTR based on the Optimum Integral Design* for EIC.**
 - A New Medium Field Superconducting Magnet for the EIC. Phase II STTR, DE-SC0021578, April 2022 \$1,1500,000, ([Summary](#), [Narrative](#), [Presentations](#))
- **Iterated design is waiting for the new magnet parameters**
- **One slide each on (1) the summary of the STTR design and on (2) the test**

* <https://wpw.bnl.gov/rgupta/optimum-integral/>




Magnetic Design of the 12 Layer OI D B0ApF



Key Parameters:

- Coil id, od: 114, 183 mm
- Coil length: 600 mm
- B_o , B_{pk} : 3.9T, 4.3T @470A
- Integral field: 1.98 T.m
- Inductance: ~700 mH
- 12 Layers (6 + 6)
- **Intermediate SS tube**

Surface contours: B
2.047697E+00



- Superconducting wire diameter: 0.33 mm
- Filament diameter: 10 μ m
- Cable type: 6-around-1
- Cable diameter (bare): 1 mm
- Cable diameter (Kapton insulated): 1.1 mm
- Critical current (4.2K, 5T): > 421 A
- Copper to superconductor ratio: 2.25
- Cable used in the magnet: 1.7 km
- Computed quench current at 4.2 K: ~500 A

Testing of the Optimum Integral Dipole B0ApF

- Magnet was energized (with **NO** spontaneous quench) to ~2.9 T (~74% of the required field integral for B0ApF at that time; requirement now reduced)
- Test seems to be limited by a superconducting lead from magnet to top hat (should be fixed in next run)
- Magnet is getting ready for re-test after the repair

